

BOTANICAL NAME			COMMON NAME			SIZE		NOTES						
Schedule														
Symbol	Label	QTY	Manufacturer	Catalog Number	Description	Lamp	Filename	Lumens per Lamp	LLF	Wattage	Distribution	Polar Plot		
	D1	26	Generation Brands	700WSPITSH-LED830	Pitch Single LED Wall Sconce; mounted at 6ft above ground	LED	102171228CHI-032 GB 700OWSPITSC-LED830.ies	803	0.9	26.2				
	D2	20	Generation Brands	700WSPITSH-LED830	Pitch Single LED Wall Sconce; mounted at 6ft above deck	LED	102171228CHI-032 GB 700OWSPITSC-LED830.ies	803	0.9	26.2				
	D3	10	Generation Brands	700WSPITSH-LED830	Pitch Single LED Wall Sconce; mounted at 6ft above deck	LED	102171228CHI-032 GB 700OWSPITSC-LED830.ies	803	0.9	26.2				
	G1	24	Generation Brands	700OWASHH93016DHUNV	Ash 16 LED Wall Sconce; mounted at 9ft	LED	103017649CHI-058 GB 700OWASHH93016DZUNVS.ies	1346	0.9	18.2				
	S1	10	Luminaire LED	TSL9 15IN 15W 30K MVOLT OP XXX	Stair Lighter TSL9; mounted at 7ft above landing	LED	TSL9_24IN_25 W_FAM7_40K_OP.ies	16	0.45	15	DIRECT, SC-0=1.26, SC-90=1.34			
	S2	10	Luminaire LED	TSL9 15IN 15W 30K MVOLT OP XXX	Stair Lighter TSL9; mounted at 7ft above landing	LED	TSL9_24IN_25 W_FAM7_40K_OP.ies	16	0.45	15	DIRECT, SC-0=1.26, SC-90=1.34			

EXISTING SOIL

**N/E MICHAEL F. RICHARD
3 OLD COUNTY ROAD
(MAP 28 - LOT 31)**

**N/E DAVID M. HOLSCHER
1 OLD COUNTY ROAD
(MAP 28 - LOT 100)**

**N/E KAROLEE S. KOKAL-MCDERMOTT
2 HAYES STREET
(MAP 27 - LOT 39)**

**N/E JOHN A. HILTON, SR.
162 BEACH ROAD
(MAP 27 - LOT 35)**

NOTES: EVERGREEN TREE PLANTING

- ALL PLANT MATERIALS SHALL BE IN ACCORDANCE WITH THE REQUIREMENTS OF THE AMERICAN NURSERY STOCK ACT (ANSI Z60.1-2004). PLANT MATERIALS SHALL BE SET IN PLACE BY THE CONTRACTOR.
- DIG THE PLANTING HOLE TO A MINIMUM OF 2 FEET DEEPER THAN THE ROOT BALL. ADJUSTING, DO NOT DIG THE HOLE DEEPER THAN THE UPPER 1/3 OF THE ROOTBALL.
- SCARIFY THE SUBGRADE AND SIDES OF THE HOLE.
- LIFT AND SET THE TREE BY ROOT BALL ONLY. DO NOT USE TREE TRUNK AS A LEVER. SET THE TOP OF THE ROOT BALL LEVEL WITH THE FINISH GRADE OR HIGHER IF THE SOIL IS PRONE TO SETTLING.
- AFTER THE TREE IS SET IN PLACE, REMOVE EXCESS SOIL FROM THE UPPER 1/3 OF THE ROOTBALL.
- BACKFILL WITH SOIL MIXTURE 2/3 LOAM, 1/3 SAND.
- USE THREE 2" X 2" WOOD STAKES DRIVEN INTO THE GROUND. SPACE STAKES EQUALLY AROUND THE TREE AT 1/3 THE TREE HEIGHT.
- APPLY A 2" (SETTLED) DEPTH OF PINE BARK MULCH SURFACE. LEAVE A 2" SPACE AROUND THE TRUNK.
- PRUNING SHALL BE LIMITED TO DEAD, DAMAGED, OR DISEASED BRANCHES IN ACCORDANCE WITH ANSI A300 SPECIFICATIONS.
- REMOVE ANY TRUNK WRAP REMAINING AT THE TIME OF INSTALLATION.
- FILL SAUCER WITH WATER TWICE AFTER PLANTING.

