


Thank you for the opportunity to submit the following quotation. Listed below is a complete breakdown of the scope of work.

#### Scope of Work

##### Pavers – \$13,500 (Driveway permeable)

- Excavate approximately 12 inches
- Add driveway grid for extra strength
- Fill with approximately 8-10 inches of ¾ clean base stone
- **Border of pavers will be installed with concrete or plastic edging. Make sure this is in other proposals**
- Compact base rock using plate compactor
- Spread and screed 1 inches of 3/8<sup>th</sup> crush over the compacted base. **Make sure this is in other proposals (No stone dust)**
- Align the paver rows using stakes and a string.
- Tap and level the pavers in place
- Fill the joints with jointing sand to hold the pavers in place.
- Sweep away any excess sand from the paver surface.
- Apply a fine water mist to the filled joints.
- If more pavers are added SQFT will be measured and multiplied by amount charged below  
20\$xsf



homeowner

Richard B  
60 n. End Blvd  
Salisbury Ma, 01952

Robert J Merrill

74 Farm Lane  
Seabrook, NH 03874

Total amount- \$13,500

PROGRESS PAYMENTS



